

3 Garden Street, Morwell Vic 3840 ABN: 46 610 154 768

PREPARED FOR

PIVOT STOVES & HEATING



THERMAL TESTING OF THE PIVOT STOVES & HEATING ROOM SEAL FLUE 8 KIT IN A FLAT CEILING AND ROOF PENETRATION ACCORDING TO APPENDIX F OF AS/NZS2918:2018

Report Number: ASFT21086-PRELIMINARY REPORT Issue date: 15 October 2021

By: Garry W. Mooney

Report Distribution

Pivot Stoves & Heating

120 Victoria Street Nth Geelong VIC

Mr Greg Parker-Hill

ASFT Report Archive

Revision Details

| Revision | Date | Comments |
|--|------|--|
| 0 15/10/2021 Preliminary report – awaiting payment and e | | Preliminary report – awaiting payment and engineering drawings of Flue Kit |
| 7.10 | 1117 | |
| | | |
| | | SOLID FUEL TESTING |

Disclaime

This Report is intended only for the use of the individual or entity named above (Intended Recipient). ASFT is not liable to the Intended Recipient in respect of any loss, damage, cost or expense suffered as a result of reliance on the information contained in this Report or any actions taken or not taken on the basis of this Report. In particular, results presented in this Report relate exclusively to the samples selected by the Intended Recipient and no responsibility is taken for the representativeness of these samples.

This report shall not be reproduced except in full, without written approval of ASFT.

QD-001R1 Copyright © 2021 ASFT


THERMAL TESTING OF THE PIVOT STOVES & HEATING ROOM SEAL FLUE 8 KIT TO AS/NZS2918:2018 APPENDIX F

Report

The Pivot Stoves & Heating Room Seal Flue 8 kit installed in a Flat Ceiling and Roof Penetration was tested according to the joint Australian/New Zealand Standard 2918:2018, Appendix F.

The Pivot Stoves & Heating Room Seal Flue 8 kit conforms to the requirements of the joint AS/NZS 2918:2018 Standard, Appendix F when installed in a Flat Ceiling and Roof Penetration.

The Flue system was tested at the following clearances:



| Figure I – | Clearance. | Dıagram |
|------------|------------|---------|
|------------|------------|---------|

| | Mario | | And Portell |
|--------|-------------------|----------|--------------------------------------|
| Signed | | Approved | |
| Name | Garry W. Mooney | Name | Steve Marland |
| | Technical Officer | | Managing Director – Australian Solid |
| Title | | Title | Fuel Testing |
| Date | 15/10/2021 | Date | 15/10/2021 |

1. INTRODUCTION

Thermal Clearance testing of the Pivot Stoves & Heating Room Seal Flue 8 kit flue system took place on October 13 & 14, 2021 at the Australian Solid Fuel Testing Laboratory located at 3 Garden Street, Morwell, Victoria. The testing was performed by Mr G.W. Mooney and Mr S. Marland.

2. PROCEDURE

Testing was conducted as per Appendix F of AS/NZS2918;2018, Hot sites were located with the aid of an infra-red thermometer. Thermocouple tips were stapled onto the test surfaces, with black tape over the first 100 mm to facilitate consistent and accurate recording of temperatures. Thermocouple positions are shown in the table below:

| Thermocouple No. | Position | Thermocouple No. | Position |
|---------------------|--|---------------------|---|
| 1 | Flue gas temperature | 17 | RHS Wall, 250mm above Ceiling, 200mm from corner |
| 2 | Ceiling – Ring Inner Right | 18 | LHS Wall, 350mm above Ceiling, 200mm from corner |
| 3 | Ceiling – 50mm Right | 19 | RHS Wall, 350mm above Ceiling, 200mm from corner |
| 4 | Ceiling – 100mm Right | 20 | LHS Wall, 450mm above Ceiling, 200mm from corner |
| 5 | Ceiling – 150mm Right | 21 | RHS Wall, 450mm above Ceiling, 200mm from corner |
| 6 | Ceiling – 200mm Rig <mark>h</mark> t | 22 | LHS Wall, 550mm above Ceiling, 200mm from corner |
| 7 | Ceiling – Ring Inner Left | 23 | RHS Wall, 550mm above Ceiling, 200mm from corner |
| 8 | Ceiling – 50mm Left | 24 | LHS Wall, 1000mm above Ceiling, 200mm from corner |
| 9 | Ceiling – 100mm Left | 25 | RHS Wall, 1000mm above Ceiling, 200mm from corner |
| 10 | Ceiling – 150mm Left | 26 | LHS Wall, 1950mm above Ceiling, 200mm from corner |
| 11 | Ceiling – 200mm Left | 27 | RHS Wall, 1950mm above Ceiling, 200mm from corner |
| 12 | LHS Wall, 50mm above Ceiling, 200mm from corner | 28 | Roof – Ring Inner Front |
| 13 | RHS Wall, 50mm above Ceiling, 200mm from corner | 29 | Roof – Ring Inner Rear |
| 14 | LHS Wall, 150mm above Ceiling, 200mm from corner | 30 | Roof – Ring Inner Left |
| 15 | RHS Wall, 150mm above Ceiling, 200mm from corner | 31 | Roof – Ring Inner Right |
| 16 | LHS Wall, 250mm above Ceiling, 200mm from corner | 32 | Ambient temperature |

5. RESULTS

5.1 Ambient and Test Surface Temperatures

The Table below show the Ambient temperatures during testing of the Flue kit.

| Hot Fire | Flue Fire | |
|-------------|-------------|--|
| 14.9 – 17.2 | 18.9 – 20.7 | |

5.2 Hot Flue Test

The Flue kit was tested in accordance with Section F8.1 of AS/NZS2918;2018. The Flue gas temperature was maintained at $760 \pm 20^{\circ}$ C until the maximum temperatures on each surface had been reach.

Below is a table of the maximum temperatures reached above Ambient.

| Position | Thermocouple Number | Hot Fire Test (°C) |
|----------|------------------------|-----------------------|
| Ceiling | 2 | 30.7 |
| RHS Wall | 27 | 34.5 |
| LHS Wall | 13 | 43.1 |
| Roof | 31 | 54.7 |

5.3 Flue Fire Test

The Flue kit was tested in accordance with Section F8.2 of AS/NZS2918;2018. The Flue gas temperature was raised from $760 \pm 20^{\circ}$ C to $1125 \pm 20^{\circ}$ C within 10minutes, then held at $1125 \pm 20^{\circ}$ C for a period of 30minutes.

Below is a table of the maximum temperatures reached above Ambient.

| Position | Thermocouple Number | Flue Fire Test (°C) |
|----------|------------------------|------------------------|
| Ceiling | 2 | 72.8 |
| RHS Wall | 15 | 99.5 |
| LHS Wall | 14 | 98.4 |
| Roof | 28 | 99.6 |

5.4 Structural Integrity Test

The Pivot Stoves & Heating Room Seal Flue 8 kit was tested in accordance with Section F8.3 of AS/NZS2918;2018. The Flue gas temperature was raised and kept at $760 \pm 20^{\circ}$ C then raised to $1125 \pm 20^{\circ}$ C within 10minutes, then held at $1125 \pm 20^{\circ}$ C for a period of 10minutes. This process was repeated three times.

The Pivot Stoves & Heating Room Seal Flue 8 kit was dismantled the following day and the components inspected for their Structural Integrity.

No Structural Integrity issues were found.

5.4 Uncertainty of Measurement Statement

- 5.5.1 The uncertainty of distance measurement for determining clearance distances was not greater than \pm 3mm.
- 5.5.2 The uncertainty of temperature measurement during the entire test period was a maximum of \pm 2°C at a 95% confidence level.



6. FLUE KIT CONSTRUCTION DETAILS

The test results reported directly relate to the Flue kit/flue system tested. The details of the Flue kit given in this section include features which may affect safety clearances. Any change in the design/construction of this Flue kit or flue may invalidate this report. Below are the constructions details of the Flue kit:

| Flue Model: Room Seal Flue 8 kit | S | Serial No: N/A |
|---|------------------------|--|
| Manufacturer: Pivot Stoves & Hear | ting | |
| Active Flue diameter: 200mm | | Length: 1000mm |
| Material thickness: 0.5mm | | |
| | _ | m isolite board on outside of upstand for 50mm tside of ring. Made of 1.2mm galvanised steel |
| Outer Casing below Ceiling diameter | er: 250mm | Length: 340mm |
| Outer casing fixed to active and p | acked with quartz inst | ulation |
| Material Type/Thickness: 0.5mm st | ainless steel (painted | black) |
| 1st Outer Casing Above Ceiling dian | neter: 250mm | Length: 1000mm |
| Outer casing fixed to a <mark>ctive</mark> and p | acked with quartz inst | alation |
| Material Type/Thickness: <mark>0.5mm st</mark> | ainless steel | |
| ^{2nd} Outer Casing A <mark>bo</mark> ve C <mark>eilin</mark> g dia | meter: 250mm | Length: 1000mm |
| Outer ca <mark>si</mark> ng fixed <mark>to</mark> ac <mark>tive a</mark> nd p | acked with quartz inst | ulation |
| Material <mark>T</mark> ype/Thic <mark>kne</mark> ss: 0.5mm st | ainless steel | |
| Cowl Height: 270mm | iameter: 300mm | Material Type: Stainless Steel |
| | | |
| | ıg | |


7. CONCLUSION

The Pivot Stoves & Heating Room Seal Flue 8 kit installed in a Flat Ceiling and Roof Penetration conforms to the requirements of Australian/New Zealand Standard 2918:2018, when tested in accordance with Appendix F.


APPENDIX 1: Thermal images of flue during testing




Above the ceiling



Below the roof



Above Roof



Below ceiling

APPENDIX 2: Flue Kit Installation Manual Supplied with the flue kit at time of Testing

